



施工歩掛例

(10m当り)

| H | a | ブロック (個) | 労 力 (人) | | | トラッククレーン 運転時間(h) | 目地モルタル (㎡) | | | | | | | | | | | | |
|------|------|-------------|---------|-------|-------|---------------------|---------------|-----|--------|-----|--------|-----|--------|-----|--------|-----|--------|-----|--------|
| | | | 世 話 役 | 据 付 工 | 普通作業員 | | | | | | | | | | | | | | |
| 600 | 600 | 5 | 0.2 | 0.5 | 0.4 | 0.2 | 0.0025 | | | | | | | | | | | | |
| | 800 | | | | | | 0.0028 | | | | | | | | | | | | |
| | 1000 | | | | | | 0.0030 | | | | | | | | | | | | |
| | 1200 | | | | | | 0.0033 | | | | | | | | | | | | |
| | 1500 | | | | | | 0.0037 | | | | | | | | | | | | |
| 700 | 700 | 5 | | | | | 0.2 | 0.5 | 0.4 | 0.2 | 0.0029 | | | | | | | | |
| | 1000 | | | | | | | | | | 0.0033 | | | | | | | | |
| | 1200 | | | | | | | | | | 0.0035 | | | | | | | | |
| | 1500 | | | | | | | | | | 0.0039 | | | | | | | | |
| 800 | 600 | 5 | | | | | | | | | 0.2 | 0.5 | 0.4 | 0.2 | 0.0030 | | | | |
| | 800 | | | | | | | | | | | | | | 0.0033 | | | | |
| | 1000 | | | | | | | | | | | | | | 0.0035 | | | | |
| | 1200 | | | | | | | | | | | | | | 0.0038 | | | | |
| | 1500 | | | | | | | | | | | | | | 0.0042 | | | | |
| 900 | 600 | 5 | | | | | | | | | | | | | 0.2 | 0.5 | 0.4 | 0.2 | 0.0037 |
| | 800 | | | | | | | | | | | | | | | | | | 0.0040 |
| | 1000 | | | | | | | | | | | | | | | | | | 0.0043 |
| | 1200 | | | | | | | | | | | | | | | | | | 0.0046 |
| | 1500 | | 0.0051 | | | | | | | | | | | | | | | | |
| 1000 | 800 | 5 | 0.2 | 0.5 | 0.4 | 0.2 | | | | | | | | | | | | | 0.0043 |
| | 1000 | | | | | | | | | | | | | | | | | | 0.0046 |
| | 1200 | | | | | | | | | | | | | | | | | | 0.0049 |
| | 1500 | | | | | | | | | | | | | | | | | | 0.0054 |
| | 1200 | | | | | | 800 | 5 | 0.2 | 0.5 | | | | | | | | | 0.4 |
| 1000 | | 0.0052 | | | | | | | | | | | | | | | | | |
| 1200 | | 0.0056 | | | | | | | | | | | | | | | | | |
| 1500 | | 0.0060 | | | | | | | | | | | | | | | | | |
| 1800 | | 0.0064 | | | | | | | | | | | | | | | | | |
| 2000 | | 0.0068 | | | | | | | | | | | | | | | | | |
| 1500 | 1200 | 5 | | | | | 0.2 | 0.5 | | | 0.4 | 0.2 | 0.0064 | | | | | | |
| | 1500 | | | | | | | | | | | | 0.0069 | | | | | | |
| | 1800 | | | | | | | | | | | | 0.0073 | | | | | | |
| | 2000 | | | | | | | | | | | | 0.0077 | | | | | | |
| 1800 | 1000 | 5 | | | | | | | | | | | 0.3 | 1.0 | 0.8 | 0.3 | 0.0062 | | |
| | 1200 | | | | | | | | | | | | | | | | 0.0064 | | |
| | 1500 | | | | | | | | | | | | | | | | 0.0068 | | |
| | 1800 | | | | | | | | | | | | | | | | 0.0072 | | |
| | 2000 | | 0.0075 | | | | | | | | | | | | | | | | |
| | 2200 | | 0.0077 | | | | | | | | | | | | | | | | |
| | 2500 | | 0.0081 | | | | | | | | | | | | | | | | |
| 2000 | 1200 | 5 | 0.3 | 1.0 | 0.8 | 0.3 | | | | | | | | | | | 0.0070 | | |
| | 1500 | | | | | | | | 0.0074 | | | | | | | | | | |
| | 1800 | | | | | | | | 0.0077 | | | | | | | | | | |
| | 2000 | | | | | | | | 0.0080 | | | | | | | | | | |
| | 2200 | | | | | | | | 0.0083 | | | | | | | | | | |
| | 2500 | | | | | | | | 0.0087 | | | | | | | | | | |

- (注) 1. 上表歩掛例は、現場内小運搬(10m程度)を含み、敷モルタルの施工、ブロック間の接合、目地詰めまでの作業であり、床掘り、基礎コンクリート、埋戻しは含みません。
2. 現場条件等により上表により難しい場合は、別途検討願います。